



Proposed Small Cell Node B/O 2 SAN MILANO DR. **GOLETA, CA 93117**

Site ID: ATTSBW02 USID: 178107



PROJECT DESCRIPTION

- INSTALL (1) OMNI DIRECTIONAL ANTENNA AND (N) ARM MOUNT ON
- (E) WOOD UTILITY POLE INSTALL (3) RRUS-2203 WITHIN NEW ENCLOSURE ON (E) WOOD UTILITY POLE
- INSTALL (N) CROWN CASTLE STRAND & FIBER ON (E) WOOD UTILITY POLE
- INSTALL (3) DOWN-CONVERTER UNITS ON (N) CROWN CASTLE

PROJECT SUMMARY

SITE ADDRESS: B/O 2 SAN MILANO DR. GOLETA, CA 93117

APPLICANT:

CROWN CASTLE NG WEST, LLC 695 RIVER OAKS PARKWAY SAN JOSE, CA 95134 CONTACT: SHARON JAMES PHONE: (408) 468-5553

CIVIL ENGINEER:

INFINIGY 26455 RANCHO PARKWAY SOUTH LAKE FOREST, CA 92630 CONTACT: JUSTIN DEHART PHONE: (949) 310-6233 FAX: (949) 753-8833

POWER/UTILITY:


2885 FOOTHILL BLVD. RIALTO, CA 92376

OFFICE: TBD CELL: TBD OFFICE: 909,873,6814

LATITUDE (NAD 83):

N 34° 25' 58,1952"

LONGITUDE (NAD 83): W 119° \$3' 6,8892"



NOT TO SCALE

T-1	TITLE PAGE, LOCATION MAP, NODE PLACEMENT					
T-2	GENERAL NOTES					
D-1	EQUIPMENT DETAILS					
D-2	EQUIPMENT DETAILS					
D-3	EQUIPMENT DETAILS					
A-1	ATTSBW02 SITE PLAN, ENLARGED SITE PLAN					
A-2	ATTSBW02 EXISTING POLE ELEVATIONS					
А-З	ATTSBW02 PROPOSED POLE ELEVATIONS					
TC-1	ATTSBW02 TRAFFIC CONTROL PLAN					
SIM1	ATTSBW02 VIEW 1 (EXISTING)					
SIM2	ATTSBW02 VIEW 1 (PROPOSED)					
SIM3	ATTSBW02 VIEW 2 (EXISTING)					
SłM4	ATTSBW02 VIEW 2 (PROPOSED)					

APPLICABLE CODES

ALL WORK SHALL COMPLY WITH THE FOLLOWING APPLICABLE CODES:

- 2016 CALIFORNIA BUILDING CODE
- 2016 CALIFORNIA MECHANICAL CODE
- 2016 CALIFORNIA PLUMBING CODE
- 2016 CALIFORNIA ELECTRICAL CODE

IN THE EVENT OF CONFLICT, THE MOST RESTRICTIVE CODE SHALL PREVAIL

LAKE FOREST, CA 92630 OFFICE # (949) 753-8807 FAX # (949) 753-8833

JOB NUMBER: 414617

OWNER/DEVELOP



IRVINE, CA 92618

CROWN CASTLE NG WEST JOB # 414617 GOLETA

	REVISIONS						
REV	DATE		DESCR	PTION	BY		
00	05-12-17	FOR CC REVIEW			JH/DG		
01	06-19-17	100% CONSTRUCTION DRAWINGS			JD		
02	04-20-18	100% CONSTRUCTION DRAWINGS		JH			
	DRAWN BY:			CHECKED BY:	APPROVED BY:		
	JH			FC	FC		
PRO	PROJECT NUMBER:			ATTSBW02	2		
FILE	FILE NAME:			TITLE PAGE			
CAT	CATE DRAWN:			05-12-17			
SCA			AS SHOWN				

T-1

EROSION AND SEDIMENT CONTROL NOTES:

TEMPORARY EROSION/SEDIMENT CONTROL, PRIOR TO COMPLETION OF FINAL IMPROVEMENTS, SHALL BE PERFORMED BY THE CONTRACTOR OR QUALIFIED PERSON AS INDICATED BELOW.

- 1. ALL REQUIREMENTS OF THE CITY OF GOLETA "LAND DEVELOPMENT MANUAL, STORM WATER STANDARDS" MUST BE INCORPORATED INTO THE DESIGN AND CONSTRUCTION OF THE PROPOSED PUBLIC IMPROVEMENTS CONSISTENT WITH THE EROSION CONTROL PLAN AND/OR WATER POLLUTION CONTROL PLAN (WPCP), IF APPLICABLE.
- FOR STORM DRAIN INLETS, PROVIDE A GRAVEL BAG SILT BASIN IMMEDIATELY UPSTREAM OF MILET AS INDICATED ON DETAILS.
- 3. THE CONTRACTOR OF QUALIFIED PERSON SHALL BE RESPONSIBLE FOR CLEANUP OF SILT AND MUD ON ADJACENT STREET(S) AND STORM DRAIN SYSTEM DUE TO CONSTRUCTION ACTIVITY.
- 4. THE CONTRACTOR SHALL REMOVE SILT AND DEBRIS AFTER EACH MAJOR RAINFALL.
- EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAIN SEASON.
- 6. THE CONTRACTOR SHALL RESTORE ALL EROSION.SEDIMENT CONTROL DEWCES TO WORKING ORDER TO THE SATISFACTION OF THE CITY ENGINEER OR RESIDENT ENGINEER AFTER EACH RUN-OFF PRODUCING RAINFALL.
- THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY BE REQUIRED BY THE RESIDENT ENGINEER DUE TO UNFORESEEN CIRCUMSTANCES, WHICH MAY ARISE.
- 8. ALL EROSION/SEDIMENT CONTROL MEASURES PROVIDED PER THE APPROVED IMPROVEMENT PLAN SHALL BE INCORPORATED HERON. ALL EROSION/SEIOMENT CONTROL FOR INTERIN CONDITIONS SHALL BE DONE TO THE SATISFACTION OF THE SECRET CHARLES
- 9. ALL REMOVABLE PROTECTIVE DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS IMMINENT.
- THE CONTRACTOR WILL ARRANGE FOR WEEKLY MEETINGS DURING OCTOBER 1ST TO APRIL 30TH FOR PROJECT TEAM (GENERAL CONTRACTOR, QUALIFIED PERSON, EROSION CONTROL SUBCONTRACTOR IF ANY, REGINEER OF WORK, OWNER, DEVELOPE AND THE RESIDENT ENGINEER) TO EVALUATE THE ADEQUACY OF THE EROSION/SEDIMENT CONTROL MEASURES AND OTHER RELATED CONSTRUCTION ACTIVITIES.

NOTES:

- 1. CONTRACTOR TO POTHOLE ALL UTILITY CROSSINGS.
- 2. CONTRACTOR TO PLACE SNADBAGS AROUND ANY/ALL STORM DRAIN INLETS TO PREVENT CONTAMINATED WATER.
- SPOILS PILE WILL BE COVERED AND CONTAINED AND STREET WILL BE SWEPT AND CLEANED AS NEEDED.
- CONTRACTOR REPAIR DAMGAED PUBLIC IMPROVEMENTS TO THE SATISFACTION OF THE CITY ENGINEER.
- CURB & GUTTER TO BE PROTECTED IN PLACE, SIDEWALK TO BE REPLACED TO THE SATISFACTION OF THE CITY ENGINEER.
- THE CONTRACTION SHALL RESTORE THE ROADWAY BACK TO ITS ORIGINAL CONDITION SATISTFACTORY TO THE CITY ENGINEER INCLUDING, BUT NOT LIMITED TO PAVING, STRIPING, BIKE LANES, PAVEMENT LEGENDS, SIGNS, AND TRAFFIC LOOP DETECTORS.
- 7. SIDEWALK SHALL BE RESTORED/REPLACED PER CITY OF GOLETA STANDARD DRAWINGS
- 8. PEDESTRIAN RAMP WILL NOT BE DISTURBED.

ROW GROUND CONTRUCTION NOTES:

- GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, OR NON-USED VERTICALS OFF THE POLE
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH MUNICIPAL, COUNTY, STATE, FEDERAL, G095 AND G0128 STANDARDS AND REGULATIONS.
- 3. CALL USA 48 HOURS PRIOR TO EXCAVATING AT (800) 277-2600 OR 611.
- 4. ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER. 5. ALL EQUIPMENT TO BE BONDED.
- 6. METERING CABINET REQUIRES 38" CLEARANCE AT DOOR OPENING.
- 7. CAULK CABINET BASE AT PAD.

NORMAL LOCATION OF UNDERGROUND UTILITIES NOTES:

- LOCATION AND DEPTH OF EXISTING AND PROPOSED UTILITIES MUST BE PROVIDED BY THE SUBDIVIDER AND SHOWN ON ANY PLANS SUBMITTED TO THE DEPARTMENT OF PUBLIC WORKS FOR APPROVAL
- CHANGES MAY BE PERMITTED BY THE DEPARTMENT OF PUBLIC WORKS IN CASES OF CONFLICTING FACILITIES.
- CONFLICTS BETWEEN UTILITY OF COMPANIES FACILITIES, EXISTING AND PROPOSED, MUST BE MUTUALLY RESOLVED BY THE UTILITY COMPANIES.
- FOR COMMERCIAL SIDEWALKS, THE FIRE HYDRANT SHALL BE PLACED WITHIN THE SIDEWALK 1'-6" BEHIND FACE OF CURB.
- MAXIMUM 2" DIAMETER GAS MAINS MAY BE PLACED IN JOINT UTILITIES TRENCH SUBJECT TO APPROVAL OF CITY ENGINEER (IN TRACTS).

CALIFORNIA STATE CODE COMPLIANCE:


ALL WORK AND MATERIALS SHALL BE PREFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

- . 2016 CALIFORNIA ADMINISTRATIVE CODE (INCLLIDING TITLES 24 & 25) 2010.
- 2016 CALIFORNIA BUILDING CODES WHICH ADOPTS THE 2014 UBC, 2015 UMC, 2015 UPC AND THE 2014 NEC.
- BUILDING OFFICIALS & CODE ADMINISTRATORS (BOCA)
- 2016 CALIFORNIA MECHANICAL CODE
- ANSI/EIA-222-F LIFE SAFETY CODE NFPA-101
- 2016 CALIFORNIA PLUMBING CODE
- 2016 CALIFORNIA ELECTRICAL CODE
- CURRENT LOCAL BUILDING CODE
- CURRENT CITY/COUNTY ORDINANCES


ACCESSIBILITY REQUIREMENTS:
FACILITY IS UNNAMINED AND NOT FOR HUMAN HABITATION. HANDICAPPED ACCESS
REQUIREMENTS DO NOT APPLY IN ACCORDANCE WITH THE 2016 CALIFORNIA
BUILDING CODE.

FCC NOTE:
THIS WRELESS COMMUNICATION FACILITY COMPLES WITH FEDERAL STANDARDS FOR
RADIO FREQUENCY IN ACCORDANCE WITH THE TELECOMMUNICATION ACT OF 1996
AND SUBSEQUENT AMENDMENTS AND ANY OTHER REQUIREMENTS IMPOSED BY
STATE OR FEDERAL REGULATORY AGENCIES.

STORM DRAIN INLET PROTECTION



TYPICAL PROTECTION FOR INLET WITH SINGLE FLOW DIRECTION



TYPICAL PROTECTION FOR INLET WITH OPPOSING FLOW DIRECTIONS

NOTES:

- INTENDED FOR SHORT-TERM USE.
- 2. LISE TO INHIBIT NON-STORM WATER FLOW. ALLOW FOR PROPER MAINTENANCE AND CLEANUP.
- BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS COMPLETED.
- NOT APPLICABLE IN AREAS WITH HIGH SILTS AND CLAYS WITHOUT FILTER FABRIC.

LEGEND

SYMBOL. DESCRIPTION

PROPOSED

2' X 3' VAULT

NEW PEDESTAL

TRENCH AND FIBER CONDUIT

NEW STREET LIGHT

EXISTING

EXISTING STREET LIGHT

EXISTING VAULT/HANDHOLE EXISTING PEDESTAL

 \square EXISTING TRANSFORMER

STATION POINT (100' STA

EXISTING CURB RAMP

C&G ÉXISTING CURB & GUTTER

-----PL EXISTING PROPERTY LINE

B.O.C. BACK OF CURB

ABBREVIATIONS

B/EOP BACK OF EDGE OR PAVEMENT

CURB & GUTTER C&G CL CENTER LINE

EX. EXISTING FOP EDGE OF PAVEMENT

FOR FACE OF CURB

F/EOP FACE OF EDGE OF PAVEMENT PROPERTY LINE

RIGHT OF WAY

SUBDIVISION BOUNDARY

26455 RANCHO PKWY, SOUTH LAKE FOREST, CA 92630. OFFICE # (949) 753-8807 FAX # (949) 753-8833

JOB NUMBER: 414617

CROWN CASTLE 300 SPECTRUM CENTER DR. SUITE 1200 IRVINE, CA 92618

CROWN CASTLE NG WEST JOB # 414617 GOLETA


REVISIONS DATE DESCRIPTION BY FOR CC REVIEW 06-19-17 100% CONSTRUCTION DRAWINGS JD 04-20-18 100% CONSTRUCTION DRAWINGS


CHECKED BY: APPROVED BY: JH FC FC


PROJECT NUMBER: ATTSBW02 FILE NAME: **GENERAL NOTES** DATE DRAWN 05-12-17 AS SHOWN


T-2


GENERAL NOTES
















END ROAD WORK

G20-2



Calle Real



TRAFFIC CONTROL PLAN GENERAL NOTES

- ALL WORK AND MATERIALS MUST COMPLY WITH THE LATEST EDITION OF THE CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- all stripping and markings must conform to caltrans revised standard plans and specifications, including RSP a-20, details.
- THE CONTRACTOR SHALL PROVIDE ACCESS TO ALL ADJACENT PROPERTIES AND DRIVEWAYS AT ALL TIMES.
- FLASHING YELLOW BEACONS, TYPE "B", SHALL BE USED ON ALL W20-1 SIGNS AND ON ALL TYPE 18 GARRICADES ADJACENT TO THE WORK AREA OVERNIGHT.
- ALL SIGNS SHALL BE REFLECTORIZED AND OF STANDARD SIZE.
- ALL TUBULAR DELINEATORS AND CONES SHALL BE A MINIMUM HEIGHT OF 28", REFLECTORIZED, AND MAINTAINED UPRIGHT IN THE INDICATED POSITION AT ALL TIMES, AND SHALL BE REPAIRED, REPLACED OR CLEANED AS NECESSARY TO PRESERVE THEIR APPEARANCE AND CONTINUITY, A 12" HIGH-INTENSITY REFLECTORIZED SLEEVE SHALL BE INCLUDED IF DEVICES ARE USED DURING NIGHT-TIME HOURS.
- THE CONTRACTOR SHALL MAINTAIN, ON A CONTINUOUS BASIS, ALL SIGNS, DELINEATORS, BARRICADES, ETC., TO ENSURE PROPER FLOW AND SAFETY OF TRAFFIC DURING
- THE CONTRACTOR SHALL HAVE ALL SIGNS, DELINEATORS, BARRICADES, ETC., PROPERLY INSTALLED PRIOR TO COMMENCING CONSTRUCTION.
- CONSTRUCTION OPERATIONS SHALL BE CONDUCTED IN SUCH A MANNER TO CAUSE AS LITTLE INCONVENIENCE AS POSSIBLE TO ABUTTING PROPERTY OWNERS AND BUSINESSES.
- ADDITIONAL TRAFFIC CONTROLS, SIGNS, OR BARRICADES MAY BE REQUIRED IN THE FIELD.
 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PLACEMENT OF ANY ADDITIONAL DEVICES
 NECESSARY TO ENSURE SAFETY OF THE PUBLIC AND WORKERS AT ALL TIMES DURING
 CONSTRUCTION.
- EXACT LOCATION AND TYPE OF CONSTRUCTION SIGNS MAY VARY BASED ON FIELD CONDITIONS.
- MOVE CONES, DELINEATORS AND BARRICADES FROM TRAVELED WAY DURING NON-WORKING HOURS.
- REMOVE, COVER AND/OR POWER OFF ALL SIGNS DURING NON-WORKING HOURS.
- ALL CONFLICTING MARKINGS SHALL BE COVERED/REMOVED BY APPROVED METHOD PRIOR TO INSTALLATIONS OF NEW/TEMPORARY MARKINGS, ALL CONFLICTING RAISED PAVEMENT MARKERS SHALL BE REMOVED, ANY PAVEMENT DAMAGED DUE TO REMOVAL OF MARKINGS AND/OR MARKERS SHALL BE REPAIRED TO THE SATISFACTION OF THE CITY ENGINEER OR
- 15. HALF-ROAD CLOSURES REQUIRE APPROVAL BY THE DEPARTMENT OF PUBLIC WORKS. ANY PAVENENT MARKINGS AND OR RAISED PAVEMENT MARKERS REMOVED/DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO THE SATISFACTION OF THE CITY ENGINEER OR INSPECTOR.
- CONTRACTOR IS RESPONSIBLE FOR ANY/ALL DAMAGES TO EXISTING TRAFFIC SIGNAL EQUIPMENT SUCH AS INDUCTION LOOPS, DETECTORS, CONDUIT, ETC.
- CONTRACTOR SHALL CONTACT THE APPROPRIATE TRANSIT AUTHORITY 72 HOURS PRIOR TO START OF WORK TO TEMPORARILY RELOCATE AFFECTED BUS STOPS.
- ALL EXCAVATIONS SHALL BE BACKFILLED OR TRENCH-PLATED AT THE END OF EACH WORK DAY, ASPHALT RAMPS SHALL BE PLACED ARQUIND EACH TRENCH PLAT TO PREVENT THE PLATE FROM BEING DISLODGED. CONTRACTOR SHALL MONITOR AND MAINTAIN TRENCH PLATES TO ENSURE SAFETY OF THE PUBLIC AT ALL TIMES, INCLUDING NON-WORKING HOURS.
- 19. TEAR DOWN AND SET UP TEMPORARY TRAFFIC CONTROL DEVICES DAILY.

INFINIGY8 Build. Boliver.

26455 RANCHO PKWY. SOUTH LAKE FOREST, CA 92630 OFFICE # (949) 753-8807 FAX # (949) 753-8833

JOB NUMBER: 414617



CROWN CASTLE NG WEST JOB # 414617 GOLETA

REV	DATE	DESCRIPTION	BY
00	05-12-17	FOR CC REVIEW	JH/DG
01	06-19-17	100% CONSTRUCTION DRAWINGS	JD
02	04-20-18	100% CONSTRUCTION DRAWINGS	JH

PROJECT NUMBER:	ATTSBW02
FILE NAME:	TRAFFIC CONTROL
DATE DRAWN:	05-12-17
SCALE:	AS SHOWN

FC

FC

TC-1

JH

TRAFFIC CONTROL PLAN

ROAD WORK AHEAD

W20-1

SCALE:

N.T.S.